



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive

Khuruhuriya, Kapilvastu
Lumbini Province, Nepal

[Signature]
F.Y. : 2081/082
Date :

BILL OF QUANTITIES (BOQ)

Project Name : Ganeshpur Gaun Bhitra Sadak Istarunnati, Wada No 7

Location : Bijaynagar Rural Municipality-07, Ganeshpur (K.V.)

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Providing And Installation Of Information Board	No	1.00	3,000.00	Three Thousands	3,000.00	
1	Carrying out the all the lab test suggested by the site engineer	PS	1.00	8,000.00	Eight Thousands	8,000.00	
	Total PS Amount				Eleven Thousands	11,000.00	
B	CIVIL WORKS						
1	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer. (DoR SS 905)	Cum	16.47				
2	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.(DoR SS 909, 910)	Cum	13.15				
3	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.(DoR SS 1201)	Cum	16.99				

श्रीधर प्रसाद सिन्हा



4	Supply and Laying Precast Cement Concrete Behton Interlocking I- Paver (70% grey & 30% single colour) (Compressive Strength : M25 or Above, Thickness : 60mm, Dimension : 200mm*165mm*60mm) incliding stone dust base and gap fill.	Sqm	113.26			
5	One layer stone solling on foundtion/floor including watering and manual compaction work.	Cum	2.81			
6	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000)	Cum	1.50			
7	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam, lintel sill and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.Inclusive of Formworks	Cum	8.54			
8	Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	Kg	371.32			
Total Amount						
Vat @ 13% (In with Ps Amount)						
Grand Total Amount						

श्रीभाराम रिजाल
प्रमुख प्रशासकीय अधिकारी



Name of Firm :

Address :

Signature :

Seal :