



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
Khuruhuriya, Kapilvastu
Lumbini Province, Nepal



BILL OF QUANTITIES (BOQ)

Project : Chhitaidehawa Sitaran ko ghar agadi Adhuro Shiv Mandir marmat wada no 4 & Tripalnagar Durga Mandir Marmat
Programme:- Aantrik shrotof-nagad (page no. 22, s.n. 73)& Karyapalika Baithak No 7 ko Nirnay No 9 ko S.No. 8
Location : Bialynagar Rural Municipality-04, shankarpur K.V.

F.Y. : 2081/082

Location : Bialynagar Rural Municipality-04, shankarpur K.V.							
S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISION SUM						
1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting, backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works. (DoR SS 110)	PS	1.00	2,000.00	Two thousand only.	2,000.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)	PS	1.00	5,000.00	Five thousand only.	5,000.00	
	Sub-Total (A)					7,000.00	
B	CIVIL WORK						
B1	chhitaidihawa sitaraanko ghar agadi Adhuro Shiv Mandir marmat wada no 4						
1	One layer stone solling on foundation/floor including watering and manual compaction work.	Cu.m	4.49				
2	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) in foundation/floor with cement, sand and stone ballast 20 mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cu.m	2.81				
3	Chimney (bhatta) brick masonry works along with supplying bricks making cement sand mortar ratio 1:4 and construction of brick wall including haulage distance upto 30m.	Cu.m	9.70				

4	Providing and laying 12.5 mm thick plaster cement sand mortar ratio 1:4 on wall & Slab	Sq.m	129.18					
5	Supplying and applying two coat exterior weather proof emulsion paint weatherproof (apex or equivalent) with one coat exterior wall primer.	Sq.m	91.73					
B2	Tripalnagar Durga Mandir Marmat							
1	Earthwork in excavation for foundation in ordinary soil including necessary lead and lift as per instruction of site engineer..	Cum	6.62					
2	One layer stone rolling on foundation/floor including watering and manual compaction work.	Cum	4.00					
3	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) in foundation with cement, sand and stone ballast 20 mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cum	3.47					
4	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam, lintel sill and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.	Cum	1.14					
5	Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	Kg.	175.50					
6	Providing, laying and curing first class brick masonry works in cement, sand mortar (1:4) in super structure work of Ground Floor in perfect lines & level as per specification, drawings & instructions of the site engineer.	Cum	1.44					


 विजयनगर
 कार्यवाहक इंजीनियर
 बुलहरिया

श्रीमान् विजयनगर
 कार्यवाहक इंजीनियर

7	Providing, laying & curing 12.5 mm cement sand (1:4) Plastering on walls to perfect plumb, lines & level including raking the mortar joints and wetting the masonry surface all complete as per design drawings, specifications and instruction of the site engineer all complete:	Sqm	189.10				
8	Supplying and applying Two coat exterior emulsion paint with one coat primer of approved colour in outer side of building as per specifications and instruction of the site engineer.	Sqm	80.18				
9	Supplying and applying two coat interior emulsion paint with one coat interior wall primer.	Sqm	73.63				
10	Centering and shuttering with plywood for Foundation including all necessary propping, scaffolding, staging, supporting, dismantling and clearing from the site, including shuttering all complete as per design drawings, specifications and instruction of the site engineer.	Sqm	18.37				
Sub Total Amount with PS							
VAT @ 13% In With PS Amount							
Grand Total Amount with PS & VAT							

Name of Firm :

Address :

Signature :

Stamp:



Handwritten signature and blue ink stamp of the Engineer-in-Charge, Public Works Department, Government of Maharashtra.