



Bijaynagar Rural Municipality
Office of the Rural Municipal Executive
 Khuruhuriya, Kapilvastu
 Lumbini Province, Nepal
BILL OF QUANTITIES (BOQ)



निमित्त प्रमुख प्रशासकीय अधिकृत

Project Name : Shankarpur Khel Maidan Marmat Sambhar
Location : Biajnagar Rural Municipality-04, Shankarpur K.V.

F.Y. : 2081/082
Date: 2081-10-28

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISION SUM						
1	Provide and installation of project information board of size 1.20 m X 0.9 m along with iron posts including excavation, concreting, backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works. (DoR SS 110)	No.	1.00				
	Sub-Total (A)						
B	CIVIL WORKS						
1	PAINTING WORKS						
1.01	Supplying and applying Two coat exterior emulsion paint with one coat primer of approved colour in outer side of building as per specifications and instruction of the site engineer.	Sq.m	128.58				
1.02	Supplying and applying two coat interior emulsion paint with one coat interior wall primer.	Sq.m	176.05				
2	DOORS AND WINDOWS WORKS						
2.01	Providing, making and fixing of MS Metal Windows/Ventilation using (20*5) mm flat patti for frame and 10mm square rod @ 3" c/c for grilling works. approved pattern and manufacture finished with one coat of metal primer paint with approved colour as per design, drawing and instruction of site engineer.	Kg.	2.70				
3	Electrical Works						
3.01	Point wiring for light and fan. (Accessories; 2*3/20 PVC cu. wire, 1/2" HDPE Pipe, Screws, PVC Tape, Grips, pvc box, switch board etc. all complete.)	Point	15.00				
3.02	Supplying and Installation of 5W LED Bulb.	Pcs.	12.00				
3.03	48" Celing Fan Fixing & fitting All Accessories As Per Site Incharge	Pcs.	3.00				
3.04	Electrical wiring for 5Amp Power Points with switch & Socket including all labour and material like: 15 mm LDP pipe, cable wire, PVC box, metal box, switch box etc	Pcs.	4.00				
3.05	4Gang Oneway Switch	Pcs.	4.00				
3.06	MCB 6-16 Amp SP	Pcs.	3.00				
4	Sanitary/ Plumbing Works						



S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
4.01	Fitting and Fixing P.V.C Water Tank (1000 ltr.) NS and accessories all complete.	Ltr.	1,000.00				
4.02	Fitting and Fixing of 110 mm dia (UPVC) Pipe NS 206/046 (4kgf/cm2)	R.m	10.00				
4.03	15 mm CP Bib Cock (Normal).	Nos	3.00				
4.04	Fitting and Fixing White Glazed Wash Basin (55x40mm) and accessories all complete set.	Set	1.00				
4.05	Fitting and Fixing of 25 mm dia CPVC pipe	R.m	20.00				
4.06	Other necessary works as per site condition.	LS	1.00				
5	Chain Link fencing mesh fixing and fitting						
5.01	Supply, fixing and fitting 10 S.W.G G.I Chain Link 2"*2" mesh in 50mm MS Black pipe post at 2m spacing including 20*3mm flat angle all complete works.	Sqm	32.40				
6	Hand Pump Installation Works						
6.01	HDPE pipe 1.5" NS Strandard (6kg/cm2)	RM	59.00				
6.02	GI pipe 1.5" dia medium class	RM	1.00				
6.03	Hand pump (Chapakal) 4 no. head with all accessories. (Medium Nepali)	Set	1.00				
6.04	48mm P.V.C. Ribbed Well Screen (2m)	RM	2.00				
6.05	Wall and washer for chapakal	No.	2.00				
6.06	Stone soling works	Cu.m	0.27				
6.07	PCC M15 for foundation.	Cu.m	0.18				
6.08	Fitting and Fixing Water Pump (1.0 H.P. Electrical motor Single Phase) and accessories all complete.	Set	1.00				
6.09	Laying of pipes in the ground by mannual slugging method using 48 mm gi pipe.						
		0-20	RM	20.00			
		20-30	RM	10.00			
		30-40	RM	10.00			
		40-50	RM	10.00			
		50-60	RM	10.00			
	Total Amount						
	Vat @ 13%						
	Grand Total Amount						

Name of Firm :

Address :

Signature :

Seal :