

Bijaynagar Rural Municipality
Office of the Rural Municipal Executive

Khuruhuriya, Kapilvastu

Lumbini Province, Nepal

BILL OF QUANTITIES (BOQ)

Project : R.T.O Dekhi Mahadev Ward No 5 Birthing Center Samma Sadak Stornnati

Programme : antarik Shrot -nagad Yatayat Purbadhar S.No.88,Page No.24

Location : Bijaynagar Rural Municipality-05, K.V.

F.Y. : 2081/082

Date:-



S. N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Provide and installation of project information board	PS	1.00	2,000.00	Two Thousand Only	2,000.00	
2	Carry out additional tests for material and works as required and instructed by the Project Manager/ Engineer. (GCC 33.1)	PS	1.00	5,000.00	Five Thousand Only	5,000.00	
B	CONSTRUCTION OF GRAVEL ROAD						
1	Construction of Subgrade and Earthen Shoulders with approved Material (capping layer) Providing and laying sub-grade and earthen shoulders with approved Material obtained from borrow pits with all lifts & leads as per Drawing and Technical Specifications. (DoR SS 1004)	Sq.m	370.00				
2	Sub Base Course: Providing , laying , spreading, leveling and compaction of natural sand gravel sub base for carriageway and shoulder as per standard specification all complete (SS/SP-1201) and instruction of engineer	Cu.m	37.00				
3	Supply and Laying Precast Cement Concrete Behton Interlocking I- Paver (70% grey & 30% single colour) (Compressive Strength : M25 or Above, Thickness : 80mm, Dimension : 200mm*165mm*80mm) incliding stone dust base and gap fill.	Sqm	284.40				

श्रीगोपाल रिजाल
प्रमुख प्रशासकीय अधिकृत

सुदूर पश्चिम प्रदेश
गोर्खा जिल्ला
सुर्खेत नगरपालिका
सुर्खेत नगरपालिका
सुर्खेत नगरपालिका

Total Amount			
Vat @ 13%			
Grand Total Amount			

Name of Firm :

Address :

Signature :

Seal :