



Khurhuriya, Kapilvastu
Lumbini Province, Nepal

BILL OF QUANTITIES (BOQ)

Project Name : Ganeshpur Gaun Bhitra Sadak Istarunnati, Wada No 7

Location : Biajynagar Rural Municipality-07, Ganeshpur (K.V.)

F.Y. : 2081/082

Date :

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Providing And Installation Of Information Board	No	1.00	3,000.00	Three Thousands	3,000.00	
1	Carrying out the all the lab test suggested by the site engineer	PS	1.00	8,000.00	Eight Thousands	8,000.00	
B	CIVIL WORKS		Total PS Amount		Eleven Thousands	11,000.00	
1	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer. (DoR SS 905)	Cum	16.47				
2	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.(DoR SS 909, 910)	Cum	13.15				
3	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.(DoR SS 1201)	Cum	16.99				

श्रीभाराम रिजाल
प्रमुख प्रशासकीय अधिकृत



4	Supply and Laying Precast Cement Concrete Behton Interlocking I- Paver (70% grey & 30% single colour) (Compressive Strength : M25 or Above,Thickness : 60mm, Dimension : 200mm*165mm*60mm) inclding stone dust base and gap fill.	Sqm	113.26				
5	One layer stone solling on foundtion/floor including watering and manual compaction work.	Cum	2.81				
6	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000)	Cum	1.50				
7	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam, lintel sill and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.Inclusive of Formworks	Cum	8.54				
8	Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	Kg	371.32				
Total Amount							
Vat @ 13% (In with Ps Amount)							
Grand Total Amount							



[Handwritten signature]

शोभाराम रिजाल
प्रमुख प्रशासकीय अधिकृत

Name of Firm :

Address :

Signature :

Seal :