

Bijaynagar Rural Municipality

Office of the Rural Municipal Executive

Khuruhuriya, Kapilvastu

Lumbini Province, Nepal

BILL OF QUANTITIES (BOQ)

Project: Bhuwaneswari Ma.Vi. School 4 kothe Adhuro Bhawan Nirman

Programme :Nepal Sarkar Sasart Anudan & BRM Mutual Fund

Location : Bijaynagar Rural Municipality-3, Jagdishpur

F.Y. : 2081/082

Date:-

S.N	Description	Unit	Quantity	Rate, NRs.		Total (NRs.)	Remark.
				In Figure	In Words		
A	PROVISIONAL SUM						
1	Provide and installation of project information board of size 1.20 m X 0.90 m along with iron posts including excavation, concreting, backfilling etc.	Nos	1	3,000.00	Three Thousand Only	3,000.00	
2	Carry out additional tests for material and works as required and instructed by the Engineer.	Ps	1	8,000.00	Eight Thousand Only	8,000.00	
B	CIVIL WORKS					11,000.00	
1	CEMENT CONCRETE WORKS						
1.1	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam, lintel sill and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.	Cum	1.47				
2	REINFORCEMENT						
2.1	Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	kg	117.44				
3	MASONRY WORK						


श्यामराम रिजाल
प्रमुख प्रशासकीय अधिकृत



3.1	Providing, laying and curing first class brick masonry works in cement, sand mortar (1:4) in super structure work of First Floor in perfect lines & level as per specification, drawings & instructions of the site engineer.	Cum	10.92				
4	PLASTERING & POINTING WORKS						
4.1	Providing, laying & curing 12.5 mm cement sand (1:4) Plastering on walls to perfect plumb, lines & level including raking the mortar joints and wetting the masonry surface all complete as per design drawings, specifications and instruction of the site engineer all complete:	sqm	596.07				
4.2	Providing, laying & curing 12.5 mm thick cement sand (1:3) plastering in ceiling, beams surfaces including chipping & wetting the concrete surfaces finished in perfect plumb, lines and level as per drawings, specifications and instructions of the site engineer.	Sqm	31.74				
5	FLOOR FINISHING						
5.1	Providing, laying and curing 3mm thick (1:1) cement sand punning on floor of buildings on perfect line & level as per design, specification and instruction of site engineer.	Sqm	136.75				
6	DOORS AND WINDOWS WORKS						
6.1	Providing, making and fixing of 38 mm thick solid flush door (Both side 4 mm teak plywood laminated door) including 38mm saal wooden frame & all labour and material charge.all complete as per specification and instruction of site engineer	Sqm	10.20				
7	METAL/IRON WORKS						
7.1	MS grill with 20x4.5mm /10mm x10mm square iron metal strips of approved pattern and manufacture finished with one coat of metal primer paint with approved colour as per design, drawing and instruction all complete.	Kg	716.10				
7.2	Supplying & Fitting ,fixing Stainless steel (2" dia. top & 3 line 1" lower pipe,vertical post 2" dia. 1 m c/c) staircase Hand Rail including joining & fabrication all complete as per specification and instruction of Site incharge / Engineer.	RM	14.40				
8	ELECTRICAL WORKS						

श्रीमती प्रशासकीय अधिकारी



8.1	Point wiring 2*3/20 PVC cu. Wire for light and fan point 1/2" in HDEP Pipe.(Accessories; HDPE Pipe , Screws, PVC Tape, Grips, Circular box, Wire etc all complete.)	Point	16.00		
8.2	Point wiring of 2*7/22+1*3/22 PVC cu. Wire for power point in 3/4" in HDEP pipe.	Point	4.00		
8.3	Installation and Fixing of 12W Round surface panel light.	Pcs.	8.00		
8.4	Installation and Fixing of 6W Round surface panel light.	Pcs.	4.00		
8.5	Distribution board 8 way TPN made of mild steel sheet double cover locable of approved company flush type etc. all complete	Pcs.	1.00		
8.6	Installation and Fixing 16amp MCB SP	Pcs.	2.00		
8.7	Installation and Fixing 16amp MCB DP	Pcs.	1.00		
8.8	Installation and Fixing of 48 inch Ceiling fans (like Usha, Cromton Greaves or similar	Pcs.	4.00		
Total Amount					
Vat @ 13%					
Grand Total Amount					

Name of Firm :

Address :

Signature :

Seal :